

Bidding Document
For
Procurement of
Design, Supply, Installation, Testing & Commissioning of 132kV
Transmission Lines on turnkey basis (Package-5)

[Contract No.: POWERGRID/ADB/132kVTL/PTSIREP/PACKAGE-5]

Addendum No.02

(Date: 06 November, 2025)

The following changes/revisions are made in the Bidding Document, which shall form part of the Bidding Document:

Volume 1 of 3

1. Appendix-2, Price Adjustment, Section-9: Contract Forms

a) The text in **clause f-** "If no data is entered for one item in the above table, the price adjustment does not apply to the item." shall be **deleted**.

b) The Text in **clause g-**

"Any Payment resulting from price adjustment will be settled at the end of contract."

Shall be replaced by-

"Any Payment resulting from price adjustment will be settled yearly starting from the contract effective date."

Volume 2 of 3

1. Section-1: Scope of Work

Page 1-6 shall be replaced by Page nos. 1-6(1) to 1-6(5) as **Annexure-1** of Addendum-2.

2. Section-3: Description of Annex 3-6 (5) is replaced by the following text-

Annex 3-6(5): Acceptance Criteria and Permissible Limits for Concrete Work

1)	Concrete	b) Compressive strength	For pile at least two sets per tower location or one set for every 110m ³ of concreting. For pile caps, chimney and beams at least one set per tower location or one set for every 110m ³ of concreting. Each set consists of four cubes, one for 7 days testing and two for 28 days testing shall be taken.
----	----------	-------------------------	--

3. Section-3: Description of Annex 3-5 is replaced by the following text-

Annex 3-5: Field Quality Plan for Transmission Lines

No.	Description of Activity	Items to be Checked	Tests / Checks to be done	Ref. Documents	Check/Testing		Counter Check / Test by Employer	Accepting Authority in Employer
					Agency	Extent		
4.	Tower Foundation	A. Concrete works b. During concreting 2. Concrete strength	Cubes compressive strength	PWD SPEC as referred in document at Annex 3-6(5)	Casting of cubes at site. Cubes to be tested at Employer-approved lab.	For pile at least two sets per tower location or one set for every 110m3 of concreting. For pile caps, chimney and beams at least one set per tower location or one set for every 110m3 of concreting.	100% cubes for piles, 20% pile caps, beams, chimney etc. to be taken in presence of Employer's officials. 100% review of test results.	Section in charge
5.	Pile foundations	b. During concreting 2. Concrete strength	2. Cubes compressive strength	PWD SPEC as referred in document at Annex 3-6(5)	Casting of cubes at site. Cubes to be tested at Employer-approved lab.	For pile at least two sets per tower location or one set for every 110m3 of concreting. For pile caps, chimney and beams at least one set per tower location or one set for every 110m3 of concreting.	100% cubes for piles, 20% pile caps, beams, chimney etc. to be taken in presence of Employer's officials. 100% review of test results.	Section in charge.

Enclosure: Annexure-1 (Section-1: Scope of Work, Volume 2 of 3)